OFFICE OF THE EXECUTIVE ENGINEER, SHIMOGA DIVISION, SHIMOGA.

Tender Notice dated 12th September 1969.

No. DB/TDR/69-70 5788. Sealed quotation in duplicate for the Departmental design in the prescribed form with the name of work are invited from the Registered contractors in Mysore P.W.D. for the following works, and will be received by the Executive Engineer Shimoga Division, Shimoga up to 4 P.M. on 18th October 1969. The tenders will be opened on the same day in the presence of the contractors or their representives or any choose to attend. Tender forms will be sold in the Office of the Executive Engineer, Shimoga Division during office hours on all working days from 6th October 1969 to 17th October 1969 (both days inclusive) on payment of prescribed cost of the tender documents which is not refundable. The competent authority reserves the right to reject any or all tenders, without assigning reason. Further particulars can be had from this office during office hours on all working days.

Sl. No.	Name of work	No. of call.	Nature of tender.	Estimate cost of work portion put to tender.	E.M.D. Rs.	Time limit for completion of work including monsoon period.	Class of contractors eligible to tender.	Cost of tender form per set.
I	Providing flooring to main dairy building of Milk Supply Scheme at Bhadravathi. (a) Providing and fixing cast iron tiles 30x30 Cms. x 12.5 mm. size flooring over a bed of 3" thick cement concrete of 1 : 2 : 4 or (b) Supplying of cast iron tiles of size 30 Cms and 30 Cms. x 12.5 mm or (c) Labour charges for fixing cast iron tiles as per specification for flooring.	I	Item rate.	47,350	1,185	Two months	Class III & above for 69-70	Rs. 5
II	(a) Providing and fixing acid and alkali proof Mandana stone slabs of 30x30 Cms. size and $\frac{3}{4}$" to $1\frac{1}{4}$" thick hand cut but machine polished for flooring over a bed concrete of 1 : 2 : 4 7.5 Cms. thick. or (b) Supplying acid and alkali proof Mandana slabs of 30x30 Cms. and 18 mm. to 30 mm. in thickness hand cut and machine polished. or (c) Labour charges for fixing acid and alkali proof Mandana slabs of 30 Cms. x 30 Cms. and 18 mm. to 30 mm in thickness over a bed concrete of 1 : 2 : 4 for flooring.	I	Item rate.	52,050	1,300	Two months	Class III & above for 69-70	Rs. 5
III	Providing and fixing granite burnt stone slabs of 10 Cms. thick pulmane dressed or 3 line dressed over a bed of cement mortar of 1 : 3, 2.5 Cms. thick.	I	Item rate.	20,850	525	Two months	Class IV & above for 69-70	Rs. 5

1482

S. C. BORE GOWDA, *Executive Engineer.*